



CABLE COMPONENTS	
○	CABLE COMPONENTS
□	KT CONTACTS (MAJOR PARTS)
△	KT CONTENTS (INSTALLATION AIDS)
L4	LENGTH OF SEMI CONDUCTING SCREEN OF CORE
L3	LENGTH OF METALLIC SHIELDING OF CORE
L2	LENGTH OF INNER SHEATH
L1	LENGTH OF ARMOUR
LEGENDS	

21	MOPPING CLOTH
20	ALOXITE EMERY TAPE
19	NYLON STRING
18	SILICONE GREASE
17	STRESS CONTROL MASTIC
16	LUG SEALING TAPE
15	TERMINAL LUG
14	MASTIC SEALING TAPE
13	WORM DRIVE CLIPS
12	INNER SHEATH
11	ARMOUR
10	TINNED COPPER EARTH BRAID (MAIN EARTH)
9	NON-TRACKING CABLE BREAK OUT
8	STRESS CONTROL TUBING
7	NON-TRACKING WEATHER RESISTANT TUBING
6	TERMINAL SLEEVE
5	OUTER SHEATH
4	METAL SHIELD
3	SEMI CONDUCTIN SCREEN
2	INSULATION
1	CONDUCTOR
S.No.	DESCRIPTIONS

CABLE SIZE (Sq.mm)	CABLE CUTTING DIMENSIONS FOR 3 CORE CABLES				CABLE CUTTING DIMENSIONS FOR 1 CORE CABLES			
	L1	L2	L3	L4	L1	L2	L3	L4
240-400	65	10	150	25	65	10	150	25
150-185	50	10	150	25	65	10	150	25
70-120	40	10	150	25	65	10	150	25
16-50	40	10	150	25	40	10	150	25

A-1 ELECTRICALS
RAJKOT - 360001, Gujarat (India)

Title :-
**Heat Shrinkable Indoor Termination
for 11KV 3&1 Core XLPE Cables**

Drawn By: Raju Prajapati
Ckd. By: Appd. By: DATE: 23/1/09
SCALE: NTS
DRG. No: A-1/08/09