



CABLE COMPONENTS	
○	CABLE COMPONENTS
□	KIT CONTENTS (MAJOR PARTS)
△	KIT CONTENTS (INSTALLATION AIDS)
L4	LENGTH OF SEMI CONDUCTING SCREEN OF CORE
L3	LENGTH OF METALLIC SHIELDING OF CORE
L2	LENGTH OF INNER SHEATH
L1	LENGTH OF ARMOUR
LEGENDS	

22	MOPPING CLOTH
21	ALOXITE EMERY TAPE
20	NYLON STRING
19	SILICONE GREASE
18	STRESS CONTROL MASTIC
17	LUG SEALING TAPE
16	TERMINAL LUG
15	MASTIC SEALING TAPE
14	WORM DRIVE CLIPS
13	INNER SHEATH
12	ARMOUR
11	TINNED COPPER EARTH BRAID (MAIN EARTH)
10	NON-TRACKING CABLE BREAK OUT
9	RAIN SHED
8	STRESS CONTROL TUBING
7	NON-TRACKING WEATHER RESISTANT TUBING
6	TERMINAL SLEEVE
5	OUTER SHEATH
4	METAL SHIELD
3	SEMI CONDUCTIN SCREEN
2	INSULATION
1	CONDUCTOR
S.No	DESCRIPTIONS

CABLE CUTTING DIMENSIONS FOR 3 CORE CABLES					CABLE CUTTING DIMENSIONS FOR 1 CORE CABLES				
CABLE SIZE (Sq.mm)	L1	L2	L3	L4	CABLE SIZE (Sq.mm)	L1	L2	L3	L4
240-400	65	10	150	25	800-1000	65	10	150	25
150-185	50	10	150	25	400-630	65	10	150	25
70-120	40	10	150	25	185-300	65	10	150	25
16-50	40	10	150	25	70-150	40	10	150	25
					16-50	40	10	150	25

A-1 ELECTRICALS
RAJKOT - 360001, Gujarat (India)

Title :-
Heat Shrinkable Outdoor Termination For 11kV(E) 3&1 Core XLPE AB Cables

Drawn By: Raju Prajapati
CKD. BY: APPD. BY: DATE: 18/11/09
DRG. No: A-1/09/09

SCALE : NTS
ESITTON No. : 00