

240-400	65	10	150	25
120-185	65	10	150	25
70-95	65	10	150	25
25-50	50	10	150	25
CABLE SIZE (Sq.mm)	L1	L2	L3	L4
CABLE CUTTING DIMENSIONS FOR 3 CORE CABLES				

1000	65	10	150	25
630-800	65	10	150	25
240-500	65	10	150	25
70-185	65	10	150	25
25-50	50	10	150	25
CABLE SIZE (Sq.mm)	L1	L2	L3	L4
CABLE CUTTING DIMENSIONS FOR 1 CORE CABLES				


L4	LENGTH OF SEMI CONDUCTING SCREEN OF CORE
L3	LENGTH OF METALLIC SHIELDING OF CORE
L2	LENGTH OF INNER SHEATH
L1	LENGTH OF ARMOUR
LEGENDS	

17*	DETAILED INSTRUCTION MANUAL
16	RAIN SHEDS
15	TERMINAL LUGS
14*	MOPPING CLOTH
13*	ALOXITE EMARY TAPE
12*	NYLON STRING
11*	CLEANING TISSUES
10	HEAT SHRINKABLE TERMINAL SLEEVE
9	SELF VULCANISING INSULATING TAPE
8	HEAT SHRINKABLE ANTI-TRACKING TUBING
7	HEAT SHRINKABLE STRESS CONTROL TUBING
6*	SILICON GREASE
5	METAL SCREEN EARTHING MATERIAL (SMALL COPPER BRAID + SOLDER+ FLUX)
4	ARMOUR EARTHING MATERIAL (BACKUO RING + COPPER BRAID+ JUBILLEE CLAMP)
3	MASTIC SEALING TAPE
2	STRESS CONTROL MASTIC
1	HEAT SHRINKABLE NON TRACKING BREAKOUT
S.No.	DESCRIPTION OF KIT CONTENTS
NOTE *(STAR) MARKED ITEMS ARE INSTALLATION AIDS	

A-1 ELECTRICALS

RAJKOT - 360001, Gujarat (India)

HEAT SHRINKABLE INDOOR TERMINATION
FOR 24 KV 3 CORE XLPE CABLES



SCALE: NTS

ESITION No. 00

DRG. No. A-1/02/09

Drawn. By Raju Prajapati	CKD. BY	APPD. BY	DATE 08/07/09
-----------------------------	---------	----------	------------------